No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs. a. p.
8	Providing and fixing new grade stones including carving figures and painting with bed slabs, etc., complete	Each	1 8 0	23	
9	Do Index stones do ..	,,	0 6 0	23	
10	Do Reg. No. stones do ..	,,	3 0 0	1	
11	Do B. M. stones do ..	,,	2 8 0	2	
	Total Rs.				
	II. *Constructing a new 6″ dia. C. I. pipe sluice at C. S. 3 with Cill at 43.00.*				
1	Earthwork cutting open the bund and refilling the same with watering and consolidation complete	C.yd.	0 5 0	44	
2	Burnt stone jelly concrete in surki mortar (1: 1: 1: 4)	C.ft.	0 4 0	49	
3	Burnt size stone in surki mortar ..	,,	0 4 6	313	
4	Providing and fixing burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	52	
5	Cement pointing after raking joints ¾″ to 1″ deep (1 : 3 prop.)	Sqr.	3 8 0	2.40	
6	Providing and fixing C. I. pipes of 6″ dia. with Railway freight, carting to site, etc., complete ..	R.ft.	3 0 0	36	
7	Providing and fixing a new plug and rod with locking arrangement, etc., complete ..	Each.	15 0 0	1	
	Total Rs. ..				
	III. *Constructing a masonry weir at R. L. 51·00 Long 85 feet.*				
1	Earthwork excavation foundation and using the earth to bund with watering and consolidation with lead and lift, etc., complete	C.yd.	0 3 0	63	
2	Burnt stone jelly concrete in surki mortar (1 : 1 : 1 : 4)	C.ft.	0 4 0	158	
3	Burnt size stone in surki mortar	,,	0 4 6	610	
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	0 4 6	216	
5	Cement pointing after raking joints ¾″ to 1″ deep (1 : 3 prop.)	Sqr.	3 8 0	7.00	
6	Constructing new rough stone apron and wings with new jelly backing and wedging including lead of 1 mile and lift, etc., complete ..	C.yds.	1 8 0	75	
	Total Rs. ..				

C. R. IYENGAR,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 9th July 1940.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 31st July 1940, for constructing a building for Restaurant in the Law Courts Building, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of four annas only for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing a building for Restaurant in Law Courts Building, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 257 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for due fulfilment

of the contract. (Cash amount will not carry any interest.) The amount of earnest money should be paid direct to the Treasury and the duplicate Treasury chellan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 31st July 1940 at 4 P.M. The final acceptance of the tender will rest with the Government who do not bind themselves to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within two months from the date of intimation of the approval of the tender, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day of delay, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery, that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

NOTE.—(*A*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling from excavations and foundations, wherever and whenever necessary, with their own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

NOTE.—(*B*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 5,000 will have to be carried out each month.

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	3	4	0	,,
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes ..	4	8	0	,,

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specifications for all the items without exception, will not be considered.

Abstract estimate for constructing a Restaurant for Law Courts, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement with watering and consolidating ..	C.yd.	0 3 6	88	19
2	Filling in foundation with granite jelly in lime mortar. Concrete jelly to be of ½″ to ¾″ size laid in layers of not more than 6″ and tamping each layer	C.ft.	0 3 6	813	178
3	Size stone in mud for foundation and basement, with bond slabs 6′ apart including corners dressed at joist	,,	0 4 0	1,755	439
4	Burnt brick in lime mortar for superstructure including bond slabs	,,	0 4 0	1,686	422
5	Providing cement concrete slabs 1 : 2 : 4 for basement with granite jelly for cills of windows, etc.	,,	0 10 0	337	211
6	Reinforced cement concrete slabs with 1½ per cent reinforcement 1 : 2 : 4 for bressumers and lintel, etc. (granite jelly)	,,	2 0 0	175	350
7	Providing and fixing teakwooddoors 3½″×4½″ frame work 1¼″ thick shutters panelled. Acme brass fittings, rim door-locks with handles, six 6″ brass hinges and two 6 inches hooks, brass screws, tower bolts of suitable size, etc., complete	S.ft.	1 8 0	123	185
8	Providing and fixing teakwood windows with frames 3″×4″ and glazed shutters 1¼″ thick with pilkingtons pin headed glass including iron bars ¾″ diameter 4″ apart, brass hinges, brass hooks, rings, stoppages, etc., complete ..	S.ft.	1 10 0	153	249
9	Providing and fixing cement fret work ventilator as per approved design	,,	0 12 0	159	120
10	Providing and fixing burnt stone slabs 6″ thick with two line dressing and edges champhered and fixed on mortar bed for steps	,,	0 10 0	36	23

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
11	Providing R.C.C. square pillars with 1½% to 2% steel 1 : 2 : 4 jelly to be of broken granite, including plastering, base and capital mouldings, etc., complete (1′×1′×7′)	No.	15 0 0	10	150
11(*a*)	Providing and fixing brick in cement mortar square pillars, including plastering, base and capital mouldings, etc., complete (1½′×1½′×10′) ..	,,	11 0 0	6	66
12	Providing hoisting and fixing R.S. girders of B.S.S. tested including one coat of anticorrosive paint, boxing with terrace bricks in cement mortar, reinforced with galvanized steel tex net tied alround	Cwt.	16 0 0	29	464
12(*a*)	Providing reinforced cement concrete beam with 1½% to 2% steel as per specification including plastering, etc., complete	C.ft.	16 0 0	29	464
13	Roofing with R.B.C. terrace as per standard specifications for spans 10′ and below. (R.C.C. to be of broken granite jelly 1 : 2 : 4) with ⅜″ diameter reinforcement bars placed at 4½″ apart centre to centre and with negative bending movement and distribution bars and 2″ cross and longitudinal joints and 3″ layer of surki concrete 2 courses of flat tiles and ½″ thick top and ceiling plastered with coving as per design, etc. complete	Sqr.	65 0 0	13.56	881
14	Providing R.C.C. chajja with proper reinforcement and anchorage into walls projecting 3′ beyond wall top and bottom plastering including coving and throating, etc., complete	S.ft.	0 10 0	1,071	670
15	Flooring with 1½″ cement concrete over 3″ granite jelly lime mortar concrete ½″ cement plastering with red colouring cut to tile pattern with border if required, etc., complete	Sqr.	18 0 0	13.06	235
15 (*a*)	Flooring the open court yard with 1½″ cement concrete over 3″ concrete bed of granite jelly in lime mortar and cement plastering, etc. ..	,,	18 0 0	2.16	39
16	Chunam plastering smooth	,,	3 0 0	36.66	110
17	White and colour washing of approved lint ..	,,	0 5 0	47.49	15
18	Cement painting to basement with racking joints ½″ deep.	,,	3 0 0	5.21	16
19	Painting doors and windows with two coats of laboratory green	,,	4 0 0	6.48	26
20	Plain bandcornice	R.ft.	0 4 0	98	25
21	Constructing ornamental parapet wall with burnt brick in chunam mortar 9″ thick and 2′ high including plastering cornice white and colour washing, etc., complete	,,	0 14 0	96	84
22	Providing and fixing G.I. down take pipes square or circular 4″ diameter with necessary bends, shoes, clamps, funnel with gratings, etc., complete, including painting with approved tint ..	,,	0 8 0	122	61
23	Providing and fixing teakwood railings of approved design in the curved portion central hall, between pillars	,,	1 0 0	20	20

Notification dated 13th July 1940.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 30th July 1940, for constructing two Special Wards with pergola in Krishnarajendra Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of four annas for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing two Special Wards with pergola in Krishnarajendra Hospital, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 913 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment

of the contract. (Cash amount will not carry any interest.) The amount of earnest money should be paid direct to treasury and the duplicate treasury chellan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 30th July 1940 at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5. P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department within four months from the date of issue of order for the commencement of the work failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 10 per day of delay which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note—(*a*) The contractor should at his own cost—

(1) Provide, rods, stakes, ropes and labours required to setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mill and shed to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs, or measurse, shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(*b*) It is the business of the contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for woodwork for all works quoted should be based on the rates of the departmental supply. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 6,000 will have to be carried out each month.

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specifications for all the items without exception will not be considered.

Abstract estimate for constructing a building for special ward in Krishnarajendra Hospital, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation in hard gravelly soil and filling in basement	C.ft.	0 4 6	84	24
2	Broken granite jelly in lime mortar 1 : 2½ : 5	,,	0 4 0	945	236
3	Size stone in clay including 2 lines dressing for exposed portion of basement	,,	0 4 0	1,553	388
4	Burnt brick in mortar for superstructure	,,	0 4 0	1,764	440
5	Burnt stone slabs 6″ thick roughly dressed and finished and fixed	Sqr.	0 9 0	153	86
6	Burnt stone slabs 2 lines dressing including fixing	S.ft.	0 12 0	165	124
7	Cement concrete slabs for top of cills	C.ft.	0 10 0	82	51
7*a*	Cement concrete slabs for cills of windows 2″	S.ft.	0 3 0	102	19
8	Constructing exmet wall 4½″ thick with burnt brick in cement mortar at every 2nd course including plastering	Sqr.	0 8 0	865	433
9	Providing and fixing new teakwood door ⅔ panelled ⅓ glazed with ground glasses and copper oxidized fittings with parliamentary hinges and catches, etc., of approved type	S.ft.	2 4 0	259	583
10	Providing and fixing teakwood windows 3″×4″ frames with glazed shutters with ground glasses with necessary parliamentary copper oxidised hinges without iron bars with window catches, etc., complete	S.ft.	2 8 0	110	275
11	Providing teakwood ventilators with frame 3″×4″ coloured glasses (antiglare glasses) and necessary fittings	Sqr.	1 4 0	60	75
12	Constructing pillars with wirecut brick in cement mortar 1 : 4, 9″×9″ with base of 1⅛×1⅛×¼ with capitals, etc., complete	Each	7 0 0	19	133
13	Providing, hoisting and fixing R. S. girders of B. S. S. tested with one coat of anticorrosive paint	Cwt.	18 0 0	44	792
14	Roofing with reinforced joist and brick-nogged terrace with 3″ of kappi 2 courses of flat tiles top and bottom plastering, etc., complete, supported on bottom flange with reinforcement as per design	Sqr.	60 0 0	19—76	1185
15	Boxing up girders with terrace brick in cement mortar and plastering	R.ft.	0 10 0	89	56
16	Boxing up girders with terrace brick in cement mortar and plastering small	R.ft.	0 8 0	89	56
17	Chunam plastering including rounding corners	S.ft.	3 0 0	41.40	124
18	Cement skirting to walls with colour cement	R.ft.	0 3 0	106	20

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
18*a*	Dadooing the walls with polished tiles 8″ to 9″ alround	R.ft.	0 8 0	175	88
19	Calcarium washing 2 coats	Sqr.	4 8 0	63.44	285
20	White and colour washing	,,	0 5 0	13.13	4
21	Flooring with 3″ of lime concrete over 1½″ of cement concrete with plastering and finished smooth	Sqr.	22 0 0	7.99	176
22	Do with green well-polished tiles as per approved type	,,	56 0 0	761	428
23	Polishing doors and windows with 2 coats of wax polish and varnishing	,,	8 0 0	9.86	78
24	Providing dental cornice as per design existing	R.ft.	0 8 0	138	69
25	Do bond cornice	,,	0 6 0	149	56
26	Constructing parapet wall with burnt brick in mortar as per existing design	,,	0 10 0	147	92
27	Constructing plain parapet wall for the main building with base and rounding offsets	,,	0 12 0	131	98
28	Providing and fixing asbestos rain-water pipe with gratings, bends, etc., complete	,,	0 12 0	160	120
29	Providing R. C. C. chejja complete 2½′ to 3′ projection	S.ft.	0 12 0	740	555
30	Providing and fixing ornamental teakwood railings as per design	R.ft.	1 8 0	125	187
31	Painting 2 coats of laboratory green paint	R.ft.	4 0 0	7.50	30
32	Providing and fixing rimlock copper oxidized high class	No.	9 0 0	9	81
33	Providing and fixing weld mesh for ventilators	S.ft.	0 12 0	56	42
	For constructing two blocks as per above details.				
	Constructing a pergola for the proposed Special Ward in the compound of Krishnarajendra Hospital, Mysore.				
1	Earthwork excavation for foundation and filling in basement in hard soil	C.yd.	0 4 6	30	8
2	Filling in foundation with stone jelly concrete in lime mortar	C.ft.	0 4 0	228	57
3	Burnt brick in lime mortar	,,	0 4 0	539	135
4	Cement concrete slabs	,,	0 4 0	61	38
5	Constructing pillars with wirecut brick in cement mortar with base and capital and plastering, etc., complete	Each	7 0 0	14	98
6	Providing and hoisting and fixing R. S. girders	Cwt.	18 0 0	12	216
7	Roofing with reinforced cement concrete joists and brick-nogged terrace with 3″ kappi 2 courses of flat tiles, etc., complete	Sqr.	60 0 0	1.72	103
8	Constructing parapet wall with brick in mortar and plastering, etc.	R.ft.	0 10 0	40	25
9	Providing ornamental cornice	,,	0 8 0	88	44
10	Providing R.C.C. chejja complete	S.ft.	0 12 0	160	120
11	Flooring with 3″ chunam concrete 1½″ cement concrete and ½″ coloured cement plastering, etc., complete	Sqr.	22 0 0	1.60	35
12	Boxing up girders with terrace bricks and plastering	R.ft.	0 8 0	111	56
13	Cement plastering	Sqr.	7 0 0	4.32	30
14	Providing and fixing ornamental teak wood railings	R.ft.	1 8 0	40	60
15	Providing teak wood trellis work	S.ft.	1 0 0	564	564
16	Laboratory green painting 2 coats	Sqr.	4 0 0	7.84	31
	For constructing two pergolas as above for the new special wards proposed.				
	Dismantling the existing building.				
1	Removing roofing with reepers and flat tiles, etc.	Sqr.	0 14 0	20.00	18
2	Removing teakwood work and carting to stores	C.ft.	0 1 0	50.00	3
3	Removing doors and windows and carting to stores	S.ft.	0 0 9	100	5
4	Dismantling wall and carting debris	C.ft.	0 0 3	4,000	63

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
5	Removing kadapa slabs flooring and carting to Stores	Sqr.	1 0 0	10.00	10
6	Removing burnt stone slabs	S.ft.	0 0 6	100	50
7	Carting debris	Each cart.	0 4 0	500	125

N. NARASIMHA IYENGAR,
Assistant Engineer.

SHIMOGA DIVISION.

Notification dated 13th July 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 5th August 1940, for improvements to the Ghat section of Agumbe Ghat at miles for 57, 58 and 59. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four per copy. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied bya treasury chellan for Rs. 1,500 credited to " 17 (*a*) P. W. deposits " in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for improvements to Ghat Section of Agumbe Ghat at miles 57, 58 and 59 " in default of which, tender will be rejected.

5. The final acceptance of any tender will rest with the Government who does not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy Brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract estimate for improvements to the Ghat section of Agumbe ghat new works proposed for 1940-41.

Item No.	Description of work	Mile	Fg.	Rate	Contents
				Rs. a. p.	
1	Widening the road width to 18′ by blasting H. R. and F. R. below the sunset platform	57	8	3 0 0	910 C.yds.
2	(*a*) Trimming the nose by earthwrok widening.. ..	58	1	0 4 0	87 ,,
	(*b*) Removing the narrow kink for widening the road (hard rock blasting)	58	8	3 0 0	14 ,,
3	(*a*) Removing the hard rock by blasting projection and kink to have a clear approach for the curve ..	59	1	3 0 0	23 ,,
	(*b*) Widening the curve to 50′ length by blasting hard rock	59	3	3 0 0	662 ,,